**SPECIFICATIONS:**

- ① **DOOR:**
ALUMINUM 1/4" DIAMOND PLATE, MILL FINISH WITH AN H20 LOAD RATING FOR INFREQUENT LOW SPEED TRAFFIC WITH A MAX SPAN DEFLECTION OF L/150
- ② **FRAME:**
ALUMINUM, 1/4" EXTRUSION, GRAY PRIMER FINISH ON EXTERIOR SURFACES THAT COME INTO CONTACT WITH CONCRETE
- ③ **HINGES:** TYPE 316 STAINLESS STEEL
- ④ **SLAM LATCH:**
TYPE 316 STAINLESS STEEL WITH INSIDE LEVER HANDLE AND OUTSIDE REMOVABLE HANDLE
- ⑤ **COUNTER-BALANCE SPRING:**
ENCLOSED, TYPE 17-7 SST SPRING
- ⑥ **HOLD-OPEN ARM:**
TYPE 316 STAINLESS STEEL WITH RED VINYL GRIP HANDLE

⑦ **FLUSH LIFT HANDLE:** TYPE 316 STAINLESS STEEL

⑧ **DRAINAGE COUPLING:** 1-1/2"

⑨ **FLUSH TYPE PLUG SEAL:** TYPE 316 STAINLESS STEEL

⑩ **GASKET:** EPDM


⑪ **SAFETY GRATE:**
ALUMINUM, 6" SERRATED RAILS WITH SAFETY ORANGE POWDER COAT, LIVE LOAD OF 300PSF, SST HINGES AND INTEGRAL PADLOCK HASP


⑫ **NUT-RAIL:** ALUMINUM NUT-RAIL ON HINGE AND LATCH SIDES

FLOOR DOOR SIZE:

PROPRIETARY AND CONFIDENTIAL: THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF BABCOCK-DAVIS. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF BABCOCK-DAVIS IS PROHIBITED.

PROJECT:					
ARCHITECT:					
CONTRACTOR:					
QTY:					
PART#:					
 9300 73rd Avenue North, Brooklyn Park, MN 55428				TITLE:	
				FD, Drainable H20, Sngl Dr, Alum, 1/4" Dmd, Mill, Gutter Frame, Gray Primer, Cast-In, Safety Grate	
	NAME	DATE	SIZE	DWG. NO.	REV
DRAWN	BES	4/11/19	A	Babcock FD BFDDHA_X_SFL-SGT ShpDr	A
RELEASED	BES	4/11/19	WEIGHT:	SHEET 1 OF 2	



 babcockdavis				TITLE: FD, Drainable H20, Sngl Dr, Alum, 1/4" Dmd, Mill, Gutter Frame, Gray Primer, Cast-In, Safety Grate		
9300 73rd Avenue North Brooklyn Park, MN 55428				DWG. NO. Babcock FD BFDDHA_X_SFL-SGT ShpDr		REV A
	NAME	DATE	SIZE			
DRAWN	BES	4/11/19	A			
RELEASED	BES	4/11/19	WEIGHT:	SHEET 2 OF 2		